## MAHARSHI DAYANAND UNIVERSITY, ROHTAK NOTICE INVITING QUOTATIONS

Sealed percentage/item rate quotations are hereby invited by the undersigned for and on behalf of Registrar, M.D. University, Rohtak for the below noted work from the suppliers/Agencies/Contractors/societies registered with Haryana P.W.D. B & R, M.E.S. & Central P.W.D. UHBVN/DHBVN or any other State/Central Govt. Department for electrical works on dated and time in the presence of quotationers or representative who may like to be present at that time. However, preference will be given to societies first, if two or more societies participated and found eligible. DNIQ may be seen on University website or in the office of Sub-Division.

Description

App. Amt. Earnest Money Time Limit

of S/F of LED false Ceriling pound

36 watt for hibrarian office & 42600/
committee room u'n Wirekananda

Library um Mou, Rohtak!

## Conditions: -

- 1. The work will be carried out strictly in accordance with the PWD Haryana specification and approved DNIQ.
- 2. Other taxes will be deducted as applicable time to time.

Sub-Divisional Engineer (Elect.)
M.D. University, Rohtak.

Cope of the above is forwarded to the following for information and necessary action:-

The Executive Engineer, M.D. University, Rohtak

Notice Board

Contractors/Agencies

M.D. University, Rohtak.

DNIT for "S/E of LED false ceiling pannel 36 watt for Librarian office & Committee room in Vivekananda Library in MDU, Rohtak".

Sr.no	Description of items	Qty.	Unit.	Rate to be quoted by Agency
14.3.2	Supply of recess mounted 36W LED flat panel 2'*2', Lumen of above in cool day light (5700K to 6500K). Average life ≥ 50000 Hrs. Power factror ≥ 0.95, CRI ≥ 80, LED lamp efficancy ≥ 100 LM/Watt, system lumen should be ≥ 3600 and glare free opal diffuser and housing made of CRCA sheet steel finishing with epoxy powder coating Complete in all respect to the satisfaction of Enginner-incharge. Make- Philips, Havells, Bajaj	24	Each	
HSR 23.2	23.20 Fixing of LED Tube light/ 2*2 ft square panel fitting directly on wall /ceiling or false ceiling including making connections etc as required	24	Each	